

土量計算書

箇 所 名	施工 延長 m	カ 所 数	掘 削							埋 戻 し										残土 m3	舗装種別		舗装取壊しおよび仮復旧						備 考
			施工 方法	掘 削 幅		掘 削 深 m	掘削土量		床均し 面積 m2	施工 方法	埋戻厚 m	掘 削 幅		控除量 m3/m	埋 戻 し 土 量						C o d e	種別名	舗装切断 延長 m	舗装版 取壊し 面積 m2	舗装版 処分量 m3	仮復旧			
				上幅 m	下幅 m		種別毎 m3	合計 m3				上幅 m	下幅 m		種別 (種別1) m3	川砂 (種別2) m3	砕石 (種別3) m3	転用土 m3	合計 m3							舗装工 m2	路盤工 m2		
A	B	C		D=k	E=l	F=c	G=(D+E)/2*F*B*C	H	I=B*E*C		J=f or J=h+g	K=k	L=l	M= h^2*π/4	N	O=P・Q={ (K+L)/2*J-M}*B*C	P Q	R=O+P+Q	S=H-Q	T	U=b	V=B*2*C	W=B*D*C	X=W*U	Y=W	Z=W	AA		
未舗装部	288.00	1	機械	0.650	0.650	0.725	135.72			機械	0.425	0.650	0.650	0.0062	1	77.77				79.56			0.00	0.00		0.00	0.00		
			人力					135.72	187.20	機械	0.300	0.650	0.650		3			56.16	133.93										
未舗装部 防火水槽までの区間	33.00	1	機械	0.650	0.650	0.663	14.22			機械	0.363	0.650	0.650	0.0028	1	7.69				7.78			0.00	0.00		0.00	0.00		
			人力					14.22	21.50	機械	0.300	0.650	0.650		3			6.44	14.13										
未舗装部 ボブスレー乗場まで	100.00	1	機械	0.650	0.650	0.634	41.21			機械	0.334	0.650	0.650	0.0008	1	21.63				21.71			0.00	0.00		0.00	0.00		
			人力					41.21	65.00	機械	0.300	0.650	0.650		3			19.50	41.13										
車道部	61.00	1	機械	0.650	0.650	0.725	28.75			機械	0.425	0.650	0.650	0.0062	1	16.47				28.75	4	t=5cm	122.00	39.70	1.99	39.70	39.70	0.19	
			人力					28.75	39.70	機械	0.250	0.650	0.650		2		9.91		26.38										
エーデルワイス脇	24.00	1	機械							人力	0.425	0.650	0.650	0.0062	1	6.48				6.63			0.00			0.00	0.00		
			人力	0.650	0.650	0.725	11.31	11.31	15.60	人力	0.300	0.650	0.650		3			4.68	11.16										
合 計			機械				219.90 220.00		329.00	機械						123.56 124.00	9.91 10.00	82.10 82.00	226.73 227.00	144.43 145.00	1	A 交 通							
																					2	B 交 通							
																					3	町道B交通							
			人力				11.31 11.00	231.21 231.00		人力						6.48 7.00		4.68 4.00	226.73 227.00	144.43 145.00	4	簡易舗装	122.00	39.70	1.99	39.70	39.70		
																					5	歩道舗装A							
																					6	C o 舗 装					m 3		